

Ref: ISLLP/VA-PRO /2026/16-1

23/02/2026

To :

M/S. VISMA ASSOCIATES
58-C, BALAJI NAGAR, RAMANATHAPURAM
CIOMBATORE -641407

KIND ATTN: MR..V. BALAJI – MANAGING DIRECTOR (+91-9994733466)

**SUBJECT: WORK ORDER FOR MARKETING OFFICE / EXPERIENCE CENTER-TRUSS +
MANGALORE TILES ROOFING WORKS - ONE LIFE PROJECT.**

S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
A	MARKETING OFFICE				
1	Design, Supply, fabrication and erection in position of all structural members using E250 Grade MS Section for structural columns, Rafters, Base plates, Cap plates, Connection plates, etc. and Rectangular hollow sections for Bracings, anchor bolts, as per the approved drawings, design and specifications. The work includes one coat of zinc chromate primer and two coats of enamel paint, transportation, loading, unloading, necessary cranes for erection etc., required to complete the work.	10,000.00	KGS	130.00	13,00,000.00
2	Supply and fixing of Top & Bottom Mangalore Tile	2,400.00	SQFT	155.00	3,72,000.00
B	EXPERIENCE CENTER ROOFING				
1	Design, Supply, fabrication and erection in position of all structural members using E250 Grade MS Section for Structural columns, Rafters, Base plates, Cap plates, Connection plates, etc. and Rectangular hollow sections for Bracings, anchor bolts, as per the approved drawings, design and specifications. The work includes one coat of zinc chromate primer and two coats of enamel paint, transportation, loading, unloading, necessary cranes for erection etc., required to complete the work.	4,000.00	KGS	115.00	4,60,000.00
2	Supply and fixing of profile BARE galvalume 0.47mm thickness 550Mpa sheets for ROOFING as per approved drawing and colour with necessary sealant, washers, Bolts and nuts etc., to complete,	140.00	SQM	500.00	70,000.00
3	Supply and fixing of 0.47mm thickness 550Mpa profiled sheets for ACCESSORIES like Corner flasher, Trip flasher, Gutter, Gable end flasher, End flasher, Down take pipes, Canopy flasher etc.	160.00	RMT	550.00	88,000.00
Sub Total					22,90,000.00
Gst @18 %					4,12,200.00
Total					27,02,200.00



Terms and Conditions:

1. The work should be started and to be completed within in the prescribed time.
2. Billing will be done as per actual site measurement.
3. It is entirely your responsibility to take all precautions and safety measures for your workers during working time in the sites.
4. Utmost Discipline should be maintained at site
5. The Contractor should adhere to quality standards, failing which leads to penalty. And if there is any rework/alteration due to quality issues, the contractor should take the responsibility.
6. TDS as per prevailing norms will be deducted from the value of bill or advances released if PAN is available. Otherwise, TDS will be at 20%
7. The quantities mentioned are approximate only. Payment shall be paid to you for the actual quantity of work executed at the site. No increase in rate shall be applicable due to any increase/decrease in the quantity during execution.
8. Payment will be done within 15 days from the date of Approval from Project In Charge.
9. The following labor laws and the social security legislations in respect of labour should be taken care by you irrespective of labour employed by you on our sites.
 - The contract labour (regulation and abolition) act 1970
 - The employee's provident funds and miscellaneous provisions act 1952.
 - The employee's state insurance act, 1948.
 - The minimum wages act, 1948.
 - The payment of Wages Act, 1936.
 - The employee's compensation act, 1923.
 - Workers below 18 years of age will be strictly prohibited to work at site.
10. Work to be done under site engineer's supervision.
11. Measurement will be taken after completion and approval by Engineer.
12. No extra payment for rework.



13. Payment Terms

60% along with PO for Material Procurement & fabrication

35% Advance for Erection and sheet laying

5% after completion of work

14. 5 % Retention Applicable

15. Vendor has to complete All of his scope of as per agreed schedule.

16. Client Scope:

Grouting - Grouting under column base plates with high strength grout.

Power supply required for erection (if needed) to be provided.

Scaffolding if required

Labor accommodation with water & EB Facilities

PLACE OF SUPPLY :

ONELIFE VEDAPATTI

SF No 188/1, INFINIUM VEDAPATTI 1,

Vadapatti Perur Road, Hanuman Temple,

VEDAPATTI, Coimbatore, Coimbatore – 641010 Contact Person : Mohanraj

Ph: 95000 48629



BILLING & CORRESPONDENCE ADDRESS

INFINIUM SHELTERS LLP

1733/1, Second Floor, Trichy Road, Ramanathapuram,

Coimbatore, Tamil Nadu 641045

GST: 33AAJF17122C1ZT

Coordination:


You shall coordinate with our **Site in charge – Mr. Mohan +91 95000 48629** - for smooth functioning and completion of work in satisfactory manner.

Arbitration

Any dispute concerning this offer entered into by the parties shall be referred to the Arbitrator (at Coimbatore) mutually appointed by both the parties.

'As a token of acceptance of this offer, kindly acknowledge and sign this order.

Thanks, and regards,



Karthikeyan P K
Authorized Signatory

